


## 21. Security Control Module

### A: REMOVAL

- 1) Remove the heater and cooling unit assembly. <Ref. to AC-60, REMOVAL, Heater and Cooling Unit.>
- 2) Remove the security control module.
  - (1) Disconnect the connector.
  - (2) Remove the nuts, and remove the security control module.



### B: INSTALLATION

Install each part in the reverse order of removal.

**Tightening torque:**

**Security control module: 7.5 N·m (0.76 kgf-m, 5.5 ft-lb)**